

MacRorie - McHaren Company

Phone Douglas 4442

721 Crocker Building
San Francisco, Cal.

IMPORTERS AND JOBBERS
ORCHIDS AND EXOTICS
TREES, SHRUBS AND HARDY PLANTS
SEEDS AND BULBS

HEADQUARTERS FOR
PHALAENOPSIS AND PHILIPPINE ORCHIDS.

CABLE ADDRESS
RORIELA SAN FRANCISCO
CODE: A B C 5TH EDITION

SUBJECT:

Hon. Board of Supervisors.

-2-

Also we would suggest that in laying out the roads that the borders of sãil on either side of the roads and walks be left about two inches above the finished rolled surface of same, as this gives a far better appearance than if the roadway is above the borders.

It is also very important that the roadways be well bottomed, for which purpose we would recommend that rock not exceeding two inches or two and one half inches in diameter be used, as it is found that larger sizes of rock do not pack evenly, and do not form a close finish, leaving large open spaces. This bottom layer of rock should be evenly spread about five inches deep, and rolled until perfectly smooth, after which a layer of finish rock or gravel, which will pass through a half inch mesh, should be spread evenly over the entire surface about one inch deep, and rolled until in proper condition.

We estimate that the cost of this work of building roadways and walks should be in the neighborhood of \$500.00, although we are not familiar with local conditions, price of rock, etc.

In connection with the planting out of the trees and plants it is most essential that this work be undertaken by a competent and experienced man, and we would recommend that this be arranged for. Such a man is obtainable at the rate of \$5.00